

# CALL FOR TENDER

## Humanitarian Aid for Northern Iraq - Rehabilitation of School Our Ref. IRQ 1023-TND-056

Dear Sirs,

Welthungerhilfe (hereafter WHH) was established in 1962. It is today one of the largest private organizations working in the area of development cooperation and humanitarian aid in Germany. The organization is non-profit-seeking, non-partisan and non-denominational. Donations from the population at large fund our work in over 40 countries in Africa, Asia and Latin America. In addition, WHH receives grants from the Department for International Development (DFID), the Federal German Government, the European Union, the United Nations and the United States Agency for International Development.

Financed by the German Ministry of Foreign Affairs (AA) for our humanitarian aid activities in Northern Iraq, we are in the market for:

### REHABILITATION OF QASIR SERIJ SECONDARY SCHOOL IN AYADHIYA SUB-DISTRICT, TILAFAR DISTRICT, NINEWA GOVERNORATE, IRAQ

#### 1. Instructions to tenderers

By submitting a tender, tenderers fully and unreservedly accept the conditions of this call for tenders, which will constitute the governing of contract as the sole basis of this tendering procedure, whatever the tenderers own conditions of sale may be which they hereby waive. Tenderers are expected to examine carefully and comply with all instructions, forms, contract provisions and specifications contained in this tender dossier. Failure to submit a tender containing all the required information and documentation within the deadline specified will lead to the rejection of the tender.

No account can be taken of any remarks in the tender relating to the tender dossier; remarks may result in the immediate rejection of the tender without further evaluation.

#### 2. General remarks and special condition

- All materials must be new, sound, fair, in merchantable quality and in line with the technical specifications stated in the Tender Documentation.
- Visitation date is on **08 July 2019 at 11:00am**  
Meeting Point: Qasir Serij Secondary School, Qasir Serij Village.
- All communication and documentation must be performed in English.
- The company needs to be officially registered in Iraq, and provide a copy of the contractor Union ID.
- Bidders have to use WHH templates.
- The Contracting Authority holds the right to change quantities and slight changes of the technical specifications.

Dohuk, 02 July 2019

Welthungerhilfe Office  
Peshnas Street 51  
Masika Roj AVA - 99451  
City of Duhok – Z26/65/9  
Kurdistan Region of Iraq  
Republic of Iraq

Jonas Wiahl  
Country Director  
[jonas.wiahl@welthungerhilfe.de](mailto:jonas.wiahl@welthungerhilfe.de)

Deutsche Welthungerhilfe e.V.  
Friedrich-Ebert-Straße 1  
D-53173 Bonn  
Tel. +49-228-2288-0  
Fax +49-228-2288-333  
[www.welthungerhilfe.de](http://www.welthungerhilfe.de)

Patron:  
Federal President Frank-Walter Steinmeier

Supervisory Board (honorary):  
Mrs. Marlehn Thieme, President  
Prof. Dr. Joachim von Braun, Vice-President  
Norbert Geisler, Chairman of the Finance Committee  
Prof. Dr. Hartwig de Haen  
Rosa Karcher  
Dr. Stephan Reimers  
Dr. Tobias Schulz-Isenbeck

Secretary General and Chairman of the Board: Mathias Mogge

Donations account:  
Sparkasse KölnBonn  
Account No. 1115  
Sort Code 370 501 98  
IBAN: DE1537050198000001115  
BIC: COLSDE33

Mitglied von Alliance 2015,  
dem Verbund internationaler  
Hilfsorganisationen

- The Contracting Authority reserves the right to accept or reject any bid, to annul the bidding process, and to reject all bids at any time prior to contract award, without thereby incurring any liability to the affected bidder or bidders.
- The safety and security of the supplier / supplier's staff, items, equipment, during the site visit or during the implementation of the project is the sole responsibility of the supplier.
- All materials, especially sand & gravels are only allowed to be excavated from clean areas of mines and explosives.
- If there is any permission needed to access the area, the bidder is in charge of obtaining the permission letter by himself. WHH will not provide any permission letter or is facilitating nor assisting this process.

### **3. Specifications/Quantities**

All applications must comply and adhere to at least the specifications and conditions described in the BOQ (Annex V).

### **4. Site location**

All work materials and items are to be supplied DDP to **Qasir Serij Village, Ayadhiya Sub-District, Tilafar District, Ninewa Governorate, Iraq.**

The contractor will be responsible for all works including all materials, transportation, installation and connections.

All units need to be fully completed and functional and ready for hand over.

### **5. Work Schedule**

The work must start latest on end of July 2019.

The exact delivery/completion schedule will be negotiated and agreed with WHH in Duhok and will be detailed in the contract.

### **6. Ordering Party**

Deutsche Welthungerhilfe  
Peshnas Street 51  
Masika Roj AVA  
99451 Duhok, KRI

### **7. Consignee**

Deutsche Welthungerhilfe  
Peshnas Street 51  
Masika Roj AVA  
99451 Duhok, KRI

### **8. Documents**

The following documents must be submitted before tender closing date:

- Signed and stamped Tender Document. (6 Pages)
- Duly filled, signed, and stamped Pre-qualification document. (Annex I, 3 pages)
- Duly filled and signed and stamped Quotation Summary (Annex II)
- Duly filled and signed and stamped References (Annex III)
- Duly filled and signed and stamped Site Visit form (Annex IV)

- Duly filled and signed and stamped BOQ (Annex V)
- Copy of company registration in Iraq / Certificate of Establishment (شهادة التأسيس)

Following documents will be requested from the contractors after finishing the work:

- Commercial Invoice (original) in English on the letter headed paper addressed to the Ordering Party
- Acceptance of service notes signed by Consignee & Contractor

## **9. Inspection**

The Contracting Authorities shall be entitled to inspect, examine measure and test the components, materials and workmanship, and check the progress of preparation, fabrication or manufacture of anything being prepared, fabricated or manufactured for delivery under the contract, in order to establish whether the components, materials and workmanship are of the requisite quality and quantity. This shall take place at the place of manufacture, fabrication, preparation or at the place of acceptance or at such other places as may be specified in the Contract.

For the purposes of such tests and inspections, the Contractor shall:

- a) Provide to the Contracting Authorities or his representative, temporarily and free of charge, with such assistance, test samples or parts, machines, equipment, tools, labor, materials, drawings and production data as are normally required for inspection and testing.
- b) Provide access to the Contracting Authorities or his representative, at all reasonable times to the place where the tests are to be carried out.

An independent surveyor company shall also execute this inspection on quality and quantity at time and place prior or at loading (before shipment to the destination). One inspection per project will be on behalf of the Contracting Authorities. Any additional inspection shall be because of the contractor. Goods not meeting agreed quality would be rejected. In case goods are rejected, the contractor will contractually be obliged to pay already incurred fees for rejected goods and for such fees that will become payable to the inspection company due to multiple interventions and/or fruitless visits and for goods inspected but eventually remained unshipped.

## **10. Penalties**

Delivery schedule will be negotiated and fixed in order. In the event of delay in delivery caused other than by force majeure, the respective Contracting Authorities are entitled to make use of a penalty of **5/1000** per day of the total value of the work still to be completed, on the concerned delivery date. The penalty will be deducted from the invoice. In the event of incomplete delivery caused by the contracted tenderer, the respective Contracting Authority is entitled to deduct the losses from the invoice. In case of damaged cargo caused by inappropriate packaging or handling errors, the respective Contracting Authority reserves the right to deduct from the relevant order sum an amount according to the variance to the requested specification. In case the quality is not in line with specifications initially agreed by both sides, the contracted tenderer has to inform the respective Contracting Authority as soon as possible. Goods not meeting agreed quality can be rejected by the respective Contracting Authority, but if the respective Contracting Authority accept these goods, a deduction from the order sum and a penalty will be negotiated.

## **11. Guarantee**

The Contractor is obliged to fix subsequently recognized construction defects within (3) Three Months after delivery at its own cost. The Contracting Authorities shall be entitled to reserve 5% (5 per cent) of the total value of the contract to guarantee this service. Exact conditions will be negotiated and fixed in contract if needed.

## **12. Prices**

The price includes the cost of materials, transportation, installation, connections, all related work as specified in the bill of quantities, technical specifications and drawings, Taxes, ICR and overhead cost.

All prices must be indicated in **USD (United States Dollars)** currency ONLY.

Prices in other currencies are not accepted.

## **13. Payment Conditions and schedule**

Payment shall take place in **USD (United States Dollars)** currency only.

Supplier need to have USD bank account and possibility to receive international USD bank transfer.

Payments due by the respective Contracting Authorities shall be made to the bank account mentioned on the Quotation Summary (Annex II) of the tenderer and confirmed in the Contract.

The contractor is in charge of covering the bank fees. **WHH WILL NOT PAY EXTRA FOR BANK FEES.**

Payment shall be made in Cash, Cheque or Transfer against document (CAD) within twenty (20) working days from the receipt of the correctly signed and stamped documents stated in Article 8. Documents at WHH in Duhok.

Payment schedule on account shall be made in accordance with the progress of the works in accordance with achievement of following executed works:

- **1<sup>st</sup> installment:** 45% of the total amount  
According to measured works after completion of 50%
- **2<sup>nd</sup> installment:** 50% of the total amount  
According to measured works after completion of 100%
- **3<sup>rd</sup> installment (Retention):** 5% of the total amount  
To be paid within 3 three months after full acceptance of the works by WHH.

Change of the payment schedule could be done by WHH only, according to the work progress measured by WHH Engineers.

## **14. Selection Criteria**

### **Awarding criteria:**

- 70% Price
- 10% Implementation period
- 10% Related Projects (Number of Related Contracts with NGOs).
- 10% Technical Interview (**only shortlisted supplier from initial evaluation 70% Price, 10% Implementation period, 10% Related Projects will be invited for technical interview**).

The assigned points per listed criteria for the price will be calculated in reference to the obtained proportion from the best offer criteria's result in comparison to the offered value per criteria (multiplied by 0.70 respectively).

Number of Related Contracts with NGOs will be evaluated as follow:

- Please attach only your work related contracts with your bid
- If contracts are not attached, points will not be considered

1-2 Contracts	3-4 Contracts	5-6 Contracts	7-9 Contracts	10 Contracts
2 points	4 points	7 points	9 points	10 points

**Exclusion criteria:**

Any of the following documents missing or not duly filled will be considered a reason for exclusion:

- Annex I, Annex II, Annex III, Annex IV, Annex V
- Company registration documents or Contractor Union ID

**15. Tender Conditions**

The tenders, all correspondence and documents related to the tender exchanged by the tenderer and the Contracting Authorities must be written in the language of the procedure, which is English.

Quotations must specify all details according to the tender text. Incomplete offers and offers that arrive later than the deadline for reply will be automatically excluded. All responses will be opened by the Welthungerhilfe tender committee.

Suppliers who do not receive a written feedback twenty-five (25) days after expiry of the deadline have not been successful.

The deadline for receiving Questions about this tender is: **09 July 2019** at 12:00 hours Iraq Local Time.

All question or enquiries should be directed to: [tender.iraq@welthungerhilfe.de](mailto:tender.iraq@welthungerhilfe.de)

**SINCE THE SITE VISIT IS MANDATORY AND IS A REASON FOR DISQUALIFICATION, THE ANSWERS WILL BE SENT BY EMAIL ON 10 July 2019 AT 12:00 NOON IRAQ LOCAL TIME ONLY TO SUPPLIERS WHO ATTENDED THE SITE VISIT**

The Contracting Authority, in Duhok, must receive the tenders before:

**16 July 2019 at 12:00 local time**

The Tender Package must include all the documents specified in Article 8 of these Instructions and be delivered to the following address:

**Deutsche Welthungerhilfe  
Peshnas Street 51  
Masika Roj AVA, 99451 Duhok  
Republic of Iraq**

The Tender Package must be submitted in a sealed and stamped envelope with the following information:

- To Welthungerhilfe or WHH
- The reference code of this tender: **IRQ 1023-TND-056**
- The company name (Your Company)

**OFFERS SENT BY E-MAILS OR FAX WILL NOT BE ACCEPTED OR CONSIDERED.**

**The following Annexes form part of this Tender Documentation:**

- Annex I:** Pre-qualification of Suppliers
- Annex II:** Quotation Summary
- Annex III:** References
- Annex IV:** Site Visit Form
- Annex V:** Bill of Quantity (BOQ)
- Annex VI:** Drawings

## Annex I: Pre-Qualification of Suppliers *(Page 1/3)*

Company Name	
Phone Number & Email	
Legal Form	
Founded (Year)	
Established in (Country)	
Bank Details (Account Holder, Bank Name, IBAN, BIC, Swift, Currency)	
VAT-Registration Number	
Physical Address	
Name of Chief Executive Officer (CEO)	
Place and Date of Birth of CEO	
Name of Owner	
Place and Date of Birth of Owner (if individual)	
Website	
Sales & Marketing Contact	
Range of Services provided by the Company (Company Portfolio)	
For internal use of WHH only	

(Page 2/3)

## Policy Statement of Welthungerhilfe

### a. Welthungerhilfe supports the goals of the UN Global Compact

The UN Global Compact is a strategic policy initiative for businesses that are committed to aligning their operations and strategies with ten universally accepted principles in the areas of human rights, Labour, environment and anti-corruption.

#### Human Rights

- Principle 1: Businesses should support and respect the protection of internationally proclaimed human rights; and
- Principle 2: make sure that they are not complicit in human rights abuses.

#### Labour

- Principle 3: Businesses should uphold the freedom of association and the effective recognition of the right to collective bargaining;
- Principle 4: the elimination of all forms of forced and compulsory Labour;
- Principle 5: the effective abolition of child Labour; and
- Principle 6: the elimination of discrimination in respect of employment and occupation.

#### Environment

- Principle 7: Businesses should support a precautionary approach to environmental challenges;
- Principle 8: undertake initiatives to promote greater environmental responsibility; and
- Principle 9: encourage the development and diffusion of environmentally friendly technologies.

#### Anti-Corruption

- Principle 10: Businesses should work against corruption in all its forms, including extortion and bribery.

The Global Compact is global and local; private and public; voluntary yet accountable.

Further information is available on this website in different languages:

<https://www.unglobalcompact.org>

### b. Welthungerhilfe (WHH) renounces all forms of terrorism and money laundering

Welthungerhilfe renounces all forms of terrorism and will never knowingly support, tolerate or encourage terrorism or the activities of those who embrace terrorism or money laundering. Consistent with numerous United Nations Security Council resolutions, including S/RES/1269(1999), S/RES 1368(2001) and S/RES1373 (2001) and the European Union, Welthungerhilfe is firmly committed to the international fight against terrorism and in particular against the financing of terrorism. It is the policy of Welthungerhilfe to seek to ensure that none of its and its donor funds are used, directly or indirectly, to provide support to individuals or entities associated with terrorism or money laundering. Therefore, Welthungerhilfe will match their suppliers and Service providers against the Sanctions lists on a regular basis. By submitting an offer, suppliers and service providers agree to this.

(Page 3/3)

## Supplier Declaration

We, \_\_\_\_\_ (name of company) hereby declare that

- a) we are not in bankruptcy proceedings, judicial insolvency proceedings or in liquidation, that we have not ceased our commercial activities and are not in a comparable situation by virtue of similar proceedings referred to in the national legal provisions,
- b) we have not received a sanction by legally binding judgment for reasons which bring into doubt our professional reliability,
- c) We comply with our duty to pay social insurance contributions, taxes or other levies in accordance with the legal provisions of the state in which we have our office, the state of the consignee, or the state where the contract is performed. We assure that we will comply with the legislation applicable and common standards in terms of wages, social legislation and occupational safety and health.
- d) we have not received a legally binding sentence due to fraud, corruption, participation in a criminal association, or another act directed against the financial interests of the International Humanitarian Aid Community,
- e) no serious breaches of contract due to non-performance of our contractual obligations have been ascertained in connection with another contract or a contract awarded from the International Humanitarian Aid Community,
- f) we are providing you with all the information required in connection with participation in a tender,
- g) in respect of contracts which are ultimately paid for out of European Community funds, no one has accused us of breach of contract due to gross violation of our contractual obligations,
- h) we have not been excluded as a contract partner by the European Community due to ethical issues,
- i) we assure the European Commission, the European Anti-Corruption Bureau and the auditors of the European Community reasonable access on demand to our business and accounting documents for the purpose of checks and audits,
- j) we respect basic social rights and condemn child labor,
- k) We are informed that Welthungerhilfe will conduct a check to ensure that partners/suppliers do not appear on official sanctions lists of UN and the European Union.

---

Date, Company Name, Signature of Owner or CEO, Name in Block letters, Stamp

## ANNEX II: Quotation Summary

Write in English and PRICE IN USD (English numbers)  
Dully fill out all grey marked areas!

No	Description	Total Price, USD
1	Rehabilitation of Qasir Serij Secondary School in Ayadhiya Sub-District	
<b>Total Price for this tender</b>		

**TOTAL PRICE IN WORDS:**

**Bank details**

Recipient Name: \_\_\_\_\_

Bank Name : \_\_\_\_\_

Account No. : \_\_\_\_\_

SWIFT Code : \_\_\_\_\_

IBAN : \_\_\_\_\_

Implementation period (number of calendar days needed to complete the project)?

\_\_\_\_\_ Calendar days

**The offer will remain valid 30 days after submission of the offer**

I, undersigned agree, these prices are for the goods and materials meeting the requirements as indicated in Annex V of this tender and to the packing, transport, delivery and other conditions mentioned in this tender.

**Note:** Any discrepancies from the given technical requirements or other discrepancies need to be explicitly mentioned.

\_\_\_\_\_  
Name and Date

\_\_\_\_\_  
Signature and Stamp

## ANNEX III: References

Please indicate only references for related NGO's or UN contracts

No	Name of Organization	Contact person	Mobile and Email	Type of contract
1				
2				
3				
4				
5				
6				
7				

IF YOU HAVE MORE REFERENCES - PLEASE COPY AND COMPLETE THIS SAME PAGE AND CONTINUE.

References which are not written in this page, will not be considered

\_\_\_\_\_  
Name and Date

\_\_\_\_\_  
Signature and Stamp

## ANNEX IV: Site Visit

**Meeting Point:** Qasir Serij Secondary School, Qasir Serij Village

**GPS coordinates:** 36.552250, 42.515642

Visited on date:

**08 July 2019 at 11:00 am**

\_\_\_\_\_  
Company Name

\_\_\_\_\_  
Name and Date

\_\_\_\_\_  
Signature

### Conformation of visit from WHH representative:

Name: \_\_\_\_\_

Signature: \_\_\_\_\_

Date: \_\_\_\_\_

## ANNEX V: BOQ – REHABILITATION OF QASIR SERIJ SECONDARY SCHOOL IN AYADHIYA SUB-DISTRICT

<p><b>Renovation of Qasir Serij Secondary school</b> Ayadhiya sub-district, Tilafar District/ Ninawa BILL OF QUANTITIES (Technical Specifications) <b>36.552250, 42.515642</b></p>
<b>Notes:</b>
1) All the works must be executed in accordance with the Iraqi General Technical Specifications (I.G.T.S.) published by Ministry of Housing and Reconstruction/ Republic of Iraq, the drawings, contract documents and instructions of the engineer.
2) The contractor shall check all items and measurements given in the BoQ. All changes, additional quantities etc. require the written approval by the project engineer. A site assessment by the contractor is mandatory.
3) Each item type should be selected by WHH engineer and the contractor should provide sample of each item, all materials must be new and the spare parts must be available in the local market.
4) All works include labor, machinery, tools, materials, transportation and all necessary works.
5) The contractor must employ a Site engineer to be present at the project site during the execution period.
6) Contractor will take responsibility for the cost of removing or moving and re-fixing after, any obstructions in work site (electricity lines, water lines, sewer system, streets, pavement, etc.) and according to the supervisor engineer instructions.
7) All items will be tested, checked and compared with the BoQ specification after finishing the work.
8) Contractor has to fix a banner showing project name and details at the work site and according to the supervisor engineer instructions.
9) Contractor has responsible for repairing any damaged work (existing DI pipe, electric pole, ...) due to implemented work.

ITEM DESCRIPTION	Unit	Quantity	Unit price	Amount
			USD	USD

A	Class rooms and Administration				
A-1	<b>Civil Work</b>				
A-1-1	Supply all materials, tools and manpower for casting concrete for the fence foundation by concrete mix 1:2:4 and reinforced by 6 steel bars of 12mmØ and stirrups of 10mmØ, 30cm C/C, with concrete mixing 1:2:4, 0.6cm depth and 0.4cm width. The work includes removing the existing foundation.	m <sup>3</sup>	9		
A-1-2	Supply all tools, materials and laborers to build the concrete walls of the outdoor fence by solid concrete blocks (15*20*40)cm and cement-sand mortar 1:3 for the joints. The work includes removing the existing damaged walls and re-build the walls, the design of the walls should be similar to the existing walls design.	m <sup>3</sup>	20		
A-1-3	Plastering work: Provide all materials and tools for plastering the exterior walls by cement-sand 1:3 plaster and interior walls by gypsum plaster.	m <sup>2</sup>	300		
A-1-4	Tiling works: Supply all materials, machines and manpower to remove the existing damaged floor tiles surrounding the school building and tiling by new mosaic tiles with 40*40cm, 4cm thickness. The work includes leveling and laying a layer of lean concrete with 10cm thickness under tiles and filling tile joints with white cement mortar.	m <sup>2</sup>	115		
A-1-5	Painting and repairing cracks: Supply all tools, materials and manpower to paint the interior walls surfaces and roofs of class rooms, administration part, corridor and WaSH facilities by two layer of emulsion paint and two layer of oil paint (120 cm) high, and exterior walls by two layers of plastic paint, before painting; all the surfaces of walls and ceilings should be cleaned from dust, debris and stickers. The work includes repairing all cracks on the walls, 10cm of the plaster around the cracks should be removed, and cleaning the cracks by air compressors/vacuum, stuffing the cracks by KALAKIM 4004, then plastering the interior cracks by gypsum plaster mixed by KALAKIM LATEX 5005, and exterior cracks by cement-sand plaster mixed by KALAKIM LATEX 5005, a fiberglass mesh of 4*4mm should be installed before plastering, then covering the repaired cracks by white hollow PVC sheet, 5mm thickness, and fixed on walls by flatt screws.	m <sup>2</sup>	2500		

A-1-6	Waterproofing on roofs: Apply sealing product according to manufacturer's instructions and the work includes clean the roof surface by water jet and the roof should be very clean and dry before applying the material. Apply the water primer coat then the UV material (Using Kalekim 4004 structural repairing mortar , 4505 Kalekim primer, 3027 UV resistance waterproofing mortar and water proofing tape 3501 for expansion and construction joints).	m <sup>2</sup>	740		
A-1-7	Exterior paint: supply tools, materials and manpower to paint the fence walls by three layer of emulsion paint, before painting the surface of walls should be cleaned from dust, debris and stickers.	m <sup>2</sup>	950		
A-1-8	New windows: Provide all materials and tools to install PVC (black tech) windows (1.5m*2.0m) for the corridors, the design should be similar to the existing windows design and the glass of 4cm thickness.	pcs	12		
A-1-9	Door repairing: provide materials, machines, tools and manpower to repair the existing rear steel door (3m*2m), two interior doors each one (2m*2.1m), the work includes fixing the plate of the doors, replacing the existing accessories (hinges, locks and handles), then cleaning the plate and frame of the doors, removing old paint and suspended debris, then painting by two layers of oil paint.	L.S	1		
A-1-10	Door replacing: Supply tools, materials and manpower to install the new main steel gate with dimensions (3m*2m) and two new steel gates for corridor each one (2m*2m) and interior door (2m*2.1m) with the plate gauge 16, the work includes painting the gate by two layers of anti-rust and a layer of oil paint. The price include all fittings (hinges, locks and handles) needed for the installation of the door.	m <sup>2</sup>	15		
A-1-11	Ladder: providing a steel ladder for the school building. The ladder must be made from smooth square tubes 4*8cm, 3mm thickness and 80cm wide connecting the floor to the corridor roof with a minimum 25cm treads, maximum 18cm risers and 90cm height of handrail.	L.S	1		
A-1-12	Title Sign Board: Supply all materials and tools to install new sign boards beside rooms, the sign boards dimensions should be 15*20cm with a steel frame, and typing should be by flex lighting style, the price includes all fitting for insatlling the sign boards of the walls.	pcs	17		

A-1-13	Expansion joints between buildings: Supply all materials, tools and manpower to inject the expansion joints with styrofoam and install aluminum plate 20cm width and rubber between the two pieces of plates, the price includes any screws and fittings needed for the installation.	m.l	40		
<b>Sub-total</b>					
A-2	<b>Electrical Work</b>				
A-2-1	Switch plug socket: Supply tools, materials and electrician to install new switch plug (shneider, legrand or semiens) with using power cable 2*1.5mm <sup>2</sup> for lighting points and 2*2.5mm <sup>2</sup> for boilers of wash facilities to connect the plugs with SDB.	pcs	45		
A-2-2	Outlet socket: Supply tools, materials and electrecian to install new socket outlet 16 Amp(shneider, legrand or semiens) with using wire 2*2.5mm <sup>2</sup> to connect the sockets with SDB.	pcs	30		
A-2-3	Lightings: Supply tools, materials and electrician to install LED ceiling light (220 v, 50 Hz, 18 watt, round shape 8" diameter LATISH) with power cable 2*1.5 to connect the lights with switch plugs.	pcs	80		
A-2-4	Bell alert: provide and install Good quality bell alert for student corridors, the cost includes all required wires and switch plugs for installation.	pcs	2		
A-2-5	Ceiling fan: Supply tools, materials and electrician to install ceiling fan (Sharp or gosonic) 3 blades, 900mm diameter sweep fan, Maximum speed: 350 rpm, by using power cable 2*1.5mm <sup>2</sup> to connect the fans with switch plugs.	pcs	12		
A-2-6	Exhaust vent fan: Supply tools, materials and electrlician to install the exhaust fan(8", 220 v, 50 Hz, 32 watt, 210 m <sup>3</sup> /hr, Shami or gosonic) for WaSH facilities, using power cable 2*1.5 for connecting the lights with switch plugs.	pcs	12		

<b>A-2-7</b>	Main Distribution Board MDB: Supply tools, materials and electrician to establish and install EX main distribution board (shneider, general or siemens) with dimensions (1*0.7)m, the work includes installing main circuit breaker 250 amp, Ammeter, voltmeter, overheat and overload, then connecting MDB with main electricity line by power cable size (2*50)mm <sup>2</sup> .	L.S	1		
<b>A-2-8</b>	Sub-main Distribution Board: Supply tools, materials and electrician to establish and install EX distribution board (shneider, general or siemens) with dimensions (0.2*0.3), the work includes installing circuit breakers and connecting with MDB by power cable size (2*16)mm <sup>2</sup> .	pcs	2		
<b>Sub-total</b>					
<b>B</b>	<b>WASH Facilities</b>				
<b>B-1</b>	<b>Rehabilitation of the existing WaSH facilities</b>				
<b>B-1-1</b>	Sanitary works: Supply all tools, materials and plumbers to remove the existing damaged sanitation system, clean squatting pans, drain system and check for blockage, provide one western squatting pan for disabled toilet and replace steel drain manholes. Check and cleaning the outdoor manholes and replace the missing steel manhole covers for septic tanks. this work will be done for (girl toilets, boy toilets, teacher toilets and handicap toilet).	L.S	1		
<b>B-1-2</b>	Tiling work: Supply all materials, machines and manpower to remove all damaged tiles from the walls and floors of toilets then replacing by new tiles same exist tile sizes, colours and design, filling the joints by white cement mortar. The price includes Clean floors in cubicles and communal spaces with tile buffer.	L.S	1		
<b>B-1-3</b>	Secondary Ceiling: Provide materials and manpowers for fixing the secondary PVC ceilings for the toilets. The work includes fixing main metal T cross beams and hunger wires and any other fittings required for the installation.	m <sup>2</sup>	60		
<b>B-1-4</b>	Doors: Supply all materials and tools to install PVC doors for toilets with dimensions of (1.0x2.1cm), the work includes all fittings required for the installation.	pcs	15		
	Septic tank: Desludging and cleaning the existing septic tanks from waste and black water(four septic tanks each one per 3m*4m*2.5m).	L.S	1		

B-1-5	Flushing Cistern: Remove all the existing flush cistern system for all toilets, then replacing and installing by new flushing cistern toilets with all necessary fittings and requirements.	pcs	11		
B-1-6	Wash Basin: Supply and install a cermaic hand washing basins 40cmx60cm, and 90cm height, turkish made. The work includes installing water mixer, mirrors 40*60cm, steel soap baskets, steel waste bin bowl brush set and jug for each toilet.	No.	12		
<b>Sub-total</b>					
<b>B-2</b>	<b>Water</b>				
B-2-1	Water tanks: Provide and install galvanized water tank, cylindrical shape, 1500 liter, plate gauge 16, the work includes removing the existing water tanks and providing all pipes and fittings required for the installation.	pcs	8		
B-2-2	Water boiler: supply and install water boiler 150 liter (italian heater) with complete connection and accessories using flexible power cable size (3*4 mm <sup>2</sup> ) for connecting the boiler with SDB, and (plastic cable duct) for inside.	pcs	4		
B-2-3	Water cooler: Water cooler made from stainless steel good quality with storage capacity 75 liter/h, with cooling pump (220 V/50Hz) , (2 tap water opend by prussure). The price including provide and install Water cooler, electrical power, water network, drainage pipe with all fittings and necessary accessories.	pcs	2		
B-2-4	Hot & Cold water dispenser: Provide water Dispenser (Korea made or approved equivalent) with the following Specification: Rated voltage: 220-240V, Rated heating power and capacity: 550W, 1.5L/H, Rated cooling corrent and capacity: 0.75A , 5L/H, The price including water Filter and all required accessories.	pcs	1		
B-2-5	Taps: provide and install stainless steel water taps 1/2" for WaSH facilities.	pcs	20		
<b>Sub-total</b>					
<b>B-3</b>	<b>Site Cleanning</b>				

B-3-1	Supply all machines, manpower and trucks to clean inside and outside of the school from all types of waste (waste materials, black water of the septic tank, construction waste materials, bushes and jungles) then transport waste to a place indicated by the municipality.	L.s	1		
<b>Sub-total</b>					

A-1	<b>Civil work</b>	
A-2	<b>Electrical work</b>	
B-1	<b>Rehabilitation of the existing WaSH facilities</b>	
B-2	<b>Water</b>	
B-3	<b>Site cleaning</b>	
<b>TOTAL COST</b>		

<b>IMPLEMENTATION PERIOD IN CALENDAR DAY</b>	
--	--

**The offer will remain valid thirty (30) days after submission of the offer**


I, undersigned agree, these prices are for the goods meeting the requirements as indicated in Annex V of this tender and delivery, payment and other conditions mentioned in this tender.


*Note: Any discrepancies from the given technical requirements or other discrepancies need to be explicitly mentioned*

\_\_\_\_\_  
Name and Date


\_\_\_\_\_  
Signature and Stamp

## ANNEX VI: REHABILITATION OF QASIR SERIJ SECONDARY SCHOOL IN AYADHIYA SUB-DISTRICT





<b>COMMISSIONED BY:</b> Government of Iraq Nineveh Governorate	
<b>DESIGNED BY:</b> welthungerhilfe	
 <b>welt hunger hilfe</b>	
<b>LEGEND:</b>	
<b>PROJECT NAME:</b> Qasirij Secondary School	
<b>DESIGNED BY:</b> Idrees R. Abdullah	
<b>DRAWN BY:</b> Idrees R. Abdullah	
<b>CONTROLLED BY:</b> Omar Tatar	
<b>DRAWING NAME:</b> Sanitation details	
<b>SHEET NO.</b>	
02	27 May. 2019



**COMMISSIONED BY:**  
Government of Iraq  
Nineveh Governorate

**DESIGNED BY:**  
welthungerhilfe



**LEGEND:**

**PROJECT NAME:**  
Qasirij Secondary School

**DESIGNED BY:**  
Idrees R. Abdullah

**DRAWN BY:**  
Idrees R. Abdullah


**CONTROLLED BY:**  
Omar Tatar

**DRAWING NAME:**  
Handicap toilet details

**SHEET NO.**

03

27 May. 2019



**COMMISSIONED BY:**  
Government of Iraq  
Nineveh Governorate

**DESIGNED BY:**  
welthungerhilfe



**LEGEND:**

**PROJECT NAME:**  
Qasirij Secondary School

**DESIGNED BY:**  
Idrees R. Abdullah

**DRAWN BY:**  
Idrees R. Abdullah



**CONTROLLED BY:**  
Omar Tatar

**DRAWING NAME:**  
Gate Details

**SHEET NO.**

04

27 May. 2019



**COMMISSIONED BY:**  
Government of Iraq  
Nineveh Governorate

**DESIGNED BY:**  
welthungerhilfe



**LEGEND:**

**PROJECT NAME:**  
Qasirij Secondary School

**DESIGNED BY:**  
Idrees R. Abdullah

**DRAWN BY:**  
Idrees R. Abdullah

**CONTROLLED BY:**  
Omar Tatar

**DRAWING NAME:**  
Gate Details

**SHEET NO.**

05

27 May. 2019